



11893 W. Streamview Dr. Star

Estimate 10516

ISSUED: AUGUST 15, 2024 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785
CALDWELL, ID 83606
US

ESTIMATE

Task 1.0	Rate	Qty	Amount
Tile removal on floors (This will need to be done for the new tile to be installed. This is the removal of tile, hauling away and the removal of the thinset and hardibacker underneath.	\$1,775	1	\$1,775
Task 2.0	Rate	Qty	Amount
Install new tile floors (This price is for a mid grade tile. Requires new hardibacker, thinset, spacers and tile.)	\$2,445	1	\$2,445

Task 3.0	Rate	Qty	Amount
Removal of current shower(Requires capping water lines, removing walls and pan. We will dispose of)	\$1,225	1	\$1,225
Task 4.0	Rate	Qty	Amount
Installation of tile shower (Tile will go to the ceiling. Includes pan, thinset, waterproofing, hardibacker or green board, tiles and labor. Also requires new drain and valve assembly.)	\$4,365	1	\$4,365
Task 5.0	Rate	Qty	Amount
Baseboard removal and reinstall for new tile. (Touchup paint, caulk and supplies)	\$275	1	\$275
Task 6.0	Rate	Qty	Amount
Removal of tile around tub	\$325	1	\$325
Task 7.0	Rate	Qty	Amount
Reinstall tile around tub to match the shower (This requires green board on walls where the tile needs to go. All requires tile and thinset.)	\$1,245	1	\$1,245
Task 8.0	Rate	Qty	Amount
Install shiplap above vanities (removal of mirrors to put shiplap on the walls above vanity. Includes trimming out and painting.)	\$1,385	1	\$1,385
Task 9.0	Rate	Qty	Amount
Install fan and humidistat in bathroom	\$525	1	\$525

YET TO BE APPROVED

Subtotal	\$13,565.00
Total	\$13,565.00

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.