



7660 W Long Dr,Boise

Estimate 12307

ISSUED: NOVEMBER 1, 2024 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785
CALDWELL, ID 83606
US

ESTIMATE

Task 1.0	Rate	Qty	%	Amount
Contain Area for Remediation by crawl space hatch, attic hatch, in kitchen, and around window's (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place. Cost is relayed on a linear foot basis)	\$32	22	0%	\$704

Task 2.0	Rate	Qty	%	Amount
PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job).	\$75	6	0%	\$450
Task 3.0	Rate	Qty	%	Amount
Run air scrubber (An air scrubber is designed with a dual filtered system in an arear to eliminate any possible contaminates from going through the home. The air scrubber is ran on a daily based per the whole duration of the job.)	\$75	2	0%	\$150
Task 4.0	Rate	Qty	%	Amount
HEPA vacuuming (This is a pre and post process. HEPA vacuuming is a process of pulling all contaminates off a surface area. This process eliminates mold particles from a surface area with specific vacuums without contaminating the air quality of a livable space. HEPA vacuuming is normally done before and after to reassure no particles are in the space that was contaminated).	\$0.90	125	0%	\$112.50
Task 5.0	Rate	Qty	%	Amount
Treatment with anti-microbial solution in attic, several areas in crawl space, and several areas underneath kitchen cabinets that need pulled out (Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)	\$2,474	1	0%	\$2,474
Task 6.0	Rate	Qty	%	Amount
Remove countertop (counters tops will fracture due to the material being a solid piece while also being attached to the wall this might also cause damage to the drywall)	\$223	1		\$223

Task 7.0	Rate	Qty	%	Amount
Removal of lower cabinets to dry out kitchen and remediate mold growth/ Removal of plumbing so countertops can be disassembled	\$925	1		\$925
Task 8.0	Rate	Qty	%	Amount
Removal of underlayment that had gotten wet under sink in kitchen	\$55	1		\$55
Task 9.0	Rate	Qty	%	Amount
Removal of tongue and groove flooring where water had gotten in	\$35	1		\$35
Task 10.0	Rate	Qty	%	Amount
Add drying equipment (An air mover is designed to dry out areas where moisture has occurred. The equipment will run the duration of the job until the moisture content has hit the IICRC's standards for an acceptable level. This is a bigger unit and is charged on a per day basis)	\$75	3	0%	\$225
Task 11.0	Rate	Qty	%	Amount
Run a dehumidifier for 3 days to insure kitchen floor dries	\$55	3		\$165
Task 12.0	Rate	Qty	%	Amount
New underlayment in kitchen floor	\$125	1		\$125
Task 13.0	Rate	Qty	%	Amount
Put back tongue and groove flooring (if salvageable, if it is not the price does not reflect new material being bought)	\$125	1		\$125
Task 14.0	Rate	Qty	%	Amount
reinstall lower kitchen cabinets and plumbing to get ready for sink installation and new countertops throughout kitchen (this pricing includes cost of new mid-grade countertop)	\$2,125	1		\$2,125
Task 15.0	Rate	Qty	%	Amount
Add tile backsplash to all areas of the kitchen to replace old countertop that was attached to the wall (includes price of mid-grade subway tile) approximate size will be 4in x 17ft to cover preexisting backsplash	\$775	1		\$775

Task 16.0	Rate	Qty	%	Amount
Sand all interior windows that have growth on them while having treated the areas of growth beforehand, also stain and lacquer window trim	\$1,025	1		\$1,025
Task 17.0	Rate	Qty	%	Amount
cleanup growth underneath 2 sinks	\$75	1		\$75
Task 18.0	Rate	Qty	%	Amount
rebuild kitchen cabinet under sink	\$225	1		\$225

YET TO BE APPROVED

Subtotal	\$9,993.50
Total	\$9,993.50

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.