



10431 W. Ardyce Ct. Boise 83704

**Estimate 11729**

ISSUED: OCTOBER 2, 2024 BY: TYLOR DESILET

EXPIRES:

**Boise Mold Removal**

VAT

PO BOX 785  
CALDWELL, ID 83606  
US

**Attachments**



Boise Mold Removal Warranty Process Overview

ESTIMATE				
Task 1.0	Rate	Qty	%	Amount
Add eve soffit vents on each side of the garage to allow crossflow ventalation.	\$175	6		\$1,050

<b>Task 2.0</b>	<b>Rate</b>	<b>Qty</b>	<b>%</b>	<b>Amount</b>
Removal of blow-in insulation in the attic. (IICRC certification requires all mold remediation companies to remove insulation when the growth is over 10sqft. This is a square footage calculation.)	\$2.40	1904	0%	\$4,569.60
<b>Task 3.0</b>	<b>Rate</b>	<b>Qty</b>	<b>%</b>	<b>Amount</b>
Treatment with anti-microbial solution in the crawlspace under the right unit bathroom. (Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)	\$525	1	0%	\$525
<b>Task 4.0</b>	<b>Rate</b>	<b>Qty</b>	<b>%</b>	<b>Amount</b>
Treatment with anti-microbial solution in the attic. Growth is hit and miss through the attic and will be a search to reassure our 3yr. warranty remains. (Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)	\$2,745	1	0%	\$2,745
<b>Task 5.0</b>	<b>Rate</b>	<b>Qty</b>	<b>%</b>	<b>Amount</b>
Install New Batt Insulation (Insulation R-value will be determined by the standard that Idaho has set for various areas of the home and the region of the state signified through the IDAHO ENERGY CONSERVATION CODES. This is done on a square footage calculation.)	\$1.90	1904	0%	\$3,617.60
<b>Task 6.0</b>	<b>Rate</b>	<b>Qty</b>	<b>%</b>	<b>Amount</b>
PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job).	\$75	3	0%	\$225

Task 7.0	Rate	Qty	%	Amount
Contain Area for Remediation for Attic (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place. Cost is relayed on a linear foot basis)	\$22	16	0%	\$352

YET TO BE APPROVED

Subtotal	\$13,084.20
Total	\$13,084.20

#### INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

#### TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.