

264 A St. W.

Estimate 10163

VAT

ISSUED: AUGUST 8, 2024 BY: TYLOR DESILET

Boise Mold Removal

PO BOX 785 CALDWELL, ID 83606 US

Attachments



Boise Mold Removal Warranty Process Overview

ESTIMATE

EXPIRES:

Task 1.0	Rate	Qty	%	Amount
PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job).	\$75	5	0%	\$375
Task 2.0	Rate	Qty	%	Amount
Asbestos Testing (This will determine 100% if it is asbestos within the plaster.)	\$275	1		\$275
Task 3.0	Rate	Qty	%	Amount
Contain Area for Remediation in the supply room. (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place.)	\$375	1	0%	\$375
Task 4.0	Rate	Qty	%	Amount
Removal of plaster ceiling to allow for proper patch to take place on the ceiling. (This includes bagging up and hauling away. The materials will be priced for asbestos removal for the time being for a proper bid.)	\$2,775	1	0%	\$2,775
Task 5.0	Rate	Qty	%	Amount
Prep concrete on the ceiling to be able to skim coat the plaster over it. This will require a mess backing to be inserted into the area.	\$1,298	1		\$1,298
	Data	Othy	%	Amount
Task 6.0	Rate	Qty	/0	/
Task 6.0Plaster and paint ceiling area to look like the restof the ceiling. (This will require for the ceiling tomatch)	\$2,245	1	70	\$2,245
Plaster and paint ceiling area to look like the rest of the ceiling. (This will require for the ceiling to		_	%	

Task 8.0	Rate	Qty	%	Amount
Treatment with anti-microbial solution on the wall where the drywall was removed, on the flooring and the cabinet below the HVAC area. (Treatment is performed with an anti- microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)	\$2,588	1	0%	\$2,588
Task 9.0	Rate	Qty	%	Amount
Removal and replacement of the cove base where the growth has occurred.	\$125	1		\$125
Task 10.0	Rate	Qty	%	Amount
Run air scrubber (An air scrubber is designed with a dual filtered system in an arear to eliminate any possible contaminates from going through the home. The air scrubber is ran on a daily based per the whole duration of the job.)	\$75	4	0%	\$300
YET TO	D BE APPROVED			

Subtotal

Total

\$12,446.00

\$12,446.00

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.