



9441 W Sageberry Dr,Boise

**Estimate 12793**

ISSUED: DECEMBER 3, 2024 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785  
CALDWELL, ID 83606  
US

ESTIMATE

| Task 1.0  | Rate | Qty | %  | Amount |
|---|------|-----|----|--------|
| PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job). | \$75 | 2   | 0% | \$150  |

| <b>Task 2.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
|--|-------------|------------|----------|---------------|
| Run air scrubber (An air scrubber is designed with a dual filtered system in an arear to eliminate any possible contaminates from going through the home. The air scrubber is ran on a daily based per the whole duration of the job.)   | \$75        | 1          | 0%       | \$75          |
| <b>Task 3.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Contain Area for Remediation (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place. Cost is relayed on a linear foot basis) | \$175       | 1          | 0%       | \$175         |
| <b>Task 4.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Demo entire shower including( Tile, shower pan)<br>This also including hauling away and dumping debris   | \$500       | 1          |          | \$500         |
| <b>Task 5.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Removal and replacement of batt insulation.<br>(This includes bagging up the insulation and disposing of it. IICRC certification requires all mold remediation companies to remove insulation when the growth is over 10sqft. This is a square footage calculation.)   | \$150       | 1          | 0%       | \$150         |
| <b>Task 6.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Treatment with anti-microbial solution<br>(Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)                        | \$550       | 1          | 0%       | \$550         |
| <b>Task 7.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Removal of shower valves (includes reinstalment of new valves)   | \$575       | 1          |          | \$575         |
| <b>Task 8.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Install waterproof membrane for shower walls and pan (warranty for 15 years)   | \$2,035.17  | 1          |          | \$2,035.17    |

| <b>Task 9.0</b>  | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
|--|-------------|------------|----------|---------------|
| Install fan in shower with humidistat for humidity levels to stay low                                    | \$525.45    | 1          |          | \$525.45      |
| <b>Task 10.0</b>   | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Install new tiles on shower pan and walls up to the ceiling (approximately 3 -5 dollars per square foot) | \$3,350     | 1          |          | \$3,350       |
| <b>Task 11.0</b>   | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Drywall work ( includes minor repairs from shower demo)  | \$200       | 1          |          | \$200         |
| <b>Task 12.0</b>   | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Install shower glass door  | \$1,200     | 1          |          | \$1,200       |
| <b>Task 13.0</b>   | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Install trough drain   | \$525.42    | 1          |          | \$525.42      |
| <b>Task 14.0</b>   | <b>Rate</b> | <b>Qty</b> | <b>%</b> | <b>Amount</b> |
| Install Shower shelves of approximately the current shelving size  | \$513.75    | 1          |          | \$513.75      |

YET TO BE APPROVED

|          |             |
|----------|-------------|
| Subtotal | \$10,524.79 |
| Total    | \$10,524.79 |

#### INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

#### TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.