



1495 N Santa Rosa Place, Meridian 83642 (10 Work
Warranty/ 50 Warranty on Materials)

Estimate 8461

ISSUED: MAY 30, 2024 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785
CALDWELL, ID 83606
US

ESTIMATE

Task 1.0	Rate	Qty	Amount
Tear off the roof to allow for new 50yr. roof to be installed. (This will include all dumpster and labor costs)	\$3,750	1	\$3,750

Task 2.0	Rate	Qty	Amount
Installation and materials cost of 50yr. Malarkey Highlander Nex Shingles	\$21,203	1	\$21,203
50yr. Malarkey Smartstarter Strips			
50yr. Malarkey Ridgeflex 12" Hip n Ridge Cap			
2x4"x10' Dripedge			
1 unit 4x4x12" Stepflashing			
2 pcs 3x5"x10' Roof to Wall			
9 Pipe Jacks 3n4			
2 boxes 4'x12" Lomanco Ridge Vent			
20 LF Intake 9"			
3 boxes 1 1/4" Coilnails			
1 box 1 3/4" Coilnails			
3 Boxes 1" p-caps			
1 tube of caulk 1 can of paint			
Secure Start HT Ice and Water on eaves and ridge.			
(This price includes labor and materials)			

YET TO BE APPROVED

Subtotal	\$24,953.00
Total	\$24,953.00

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.