



PENDING APPROVAL

822 N. Cottage Cove Way, Star

From

Boise Mold Removal

Tylor Desilet

PO Box 785

Caldwell, ID 83606

US

Phone: 2084120899

info@boise-moldremoval.com

VAT

INVOICE #

ISSUED ON

March 14, 2025

EXPIRES ON

July 12, 2024

TOTAL ESTIMATED

\$4,470.00

Attachments



Resized_Resized_20240611_141846



Resized_Resized_20240611_141634



Resized_Resized_20240611_142702



Resized_Resized_20240611_141922



Boise Mold Removal Warranty Process Overview

Task 1.0	Rate	Qty	%	Amount
Contain Area for Remediation (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place. Cost is relayed on a linear foot basis)	\$32	12	0%	\$384

Task 2.0	Rate	Qty	%	Amount
PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job).	\$75	3	0%	\$225

Task 3.0	Rate	Qty	%	Amount
Pre and post HEPA vacuuming in the crawlspace. (HEPA vacuuming is a process of pulling all contaminates off a surface area. This process eliminates mold particles from a surface area with specific vacuums without contaminating the air quality of a livable space. HEPA vacuuming is normally done before and after to reassure no particles are in the space that was contaminated).	\$0.65	1992	0%	\$1,294.80

Task 4.0	Rate	Qty	%	Amount
Treatment with anti-microbial solution in the crawlspace on the I-beams. This is throughout the crawlspace. (Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is	\$1.10	1992	0%	\$2,191.20

warranted for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)

Task 5.0	Rate	Qty	%	Amount
Install new vapor barrier and fix areas that are needed. (Install new vapor barrier in the crawlspace. The vapor is to cover all the dirt to reassure that moisture is kept down. The vapor barrier will be done with a 6mil plastic, which is the industry standard. The cost is done on square footage.)	\$375	1	0%	\$375

YET TO BE APPROVED ESTIMATES

SUBTOTAL	\$4,470.00
TOTAL	\$4,470.00

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.