



6052 E Orchard Ave,Nampa

Estimate 12679

ISSUED: NOVEMBER 25, 2024 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785
CALDWELL, ID 83606
US

ESTIMATE

Task 1.0	Rate	Qty	%	Amount
PPE (Personal Protective Equipment) (This is safety equipment for our techs to wear during remediation practices. This is a per person per day basis. There will need to be new PPE every day for proper safety. This includes the Tyvek suits, gloves, and any filters per the duration of the job).	\$75	2	0%	\$150

Task 2.0	Rate	Qty	%	Amount
Contain Area for Remediation (Containment eliminates any contaminates from existing into the livable space. Without the containment also the insulation, if removed can possibly enter the livable space, kicking insulation, dirt and possible mold-like substance around. We can pull the containment after remediation has taken place. Cost is relayed on a linear foot basis)	\$75	1	0%	\$75
Task 3.0	Rate	Qty	%	Amount
Run air scrubber (An air scrubber is designed with a dual filtered system in an arear to eliminate any possible contaminates from going through the home. The air scrubber is ran on a daily based per the whole duration of the job.)	\$75	1	0%	\$75
Task 4.0	Rate	Qty	%	Amount
HEPA vacuuming (This is a pre and post process. HEPA vacuuming is a process of pulling all contaminates off a surface area. This process eliminates mold particles from a surface area with specific vacuums without contaminating the air quality of a livable space. HEPA vacuuming is normally done before and after to reassure no particles are in the space that was contaminated).	\$0.56	1270	0%	\$711.20
Task 5.0	Rate	Qty	%	Amount
Treatment with anti-microbial solution (Treatment is performed with an anti-microbial solution that eliminates and prevents future growth. All treatment is warrantied for 3yrs. unless Boise Mold Removal does not provide a warranty under the stipulations of the client not solving the underlying issue that caused the growth in the first place.)	\$1.20	1270	0%	\$1,524
Task 6.0	Rate	Qty	%	Amount
Crawlspace did not look like it had any growth. Various areas of ink from printing of the OSB subfloor.	\$0			\$0

Subtotal	\$2,535.20
Total	\$2,535.20

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.