



321 E Melrose St, Boise, ID 83706

Estimate 3838

ISSUED: OCTOBER 4, 2023 BY: TYLOR DESILET

EXPIRES:

Boise Mold Removal

VAT

PO BOX 785
CALDWELL, ID 83606
US

ESTIMATE

Task 1.0	Rate	Qty	%	Amount
Contain room to reassure the growth doesn't go through the house. (This is a 6mil plastic that seals the room, also the air scrubber is in the room)	\$325	1		\$325
Task 2.0	Rate	Qty	%	Amount
Flood cut downstairs walls 2 ft. up to explore where the growth is (Requires removing trim, cabinets and items in room. We will dispose of all debris)	\$550	1		\$550

Task 3.0	Rate	Qty	%	Amount
Pull and remove the carpet and tack strip in the room where the water is entering (There is growth on both the carpet and tack strip. Includes debris disposal)	\$375	1		\$375
Task 4.0	Rate	Qty	%	Amount
Remediate area that is exposed per the 2ft. cut out. (Price may vary if 2ft. cutout is different)	\$1,025	1		\$1,025
Task 5.0	Rate	Qty	%	Amount
Replace drywall with the 2ft. minimal cost. (Includes drywall, tape and texture and paint)	\$1,025	1	0%	\$1,025
Task 6.0	Rate	Qty	%	Amount
Replace the carpet in the room that the remediation was done (If the client wants something different than like carpet we will discuss it. Includes tack strip)	\$1,525	1		\$1,525
Task 7.0	Rate	Qty	%	Amount
Install the cabinets and trim back in (Include painting of the trim)	\$475	1		\$475

YET TO BE APPROVED

Subtotal	\$5,300.00
Total	\$5,300.00

INFO & NOTES

Please take a chance to review your estimate and click accept. For payments over \$1000.00, we require 50% of the payment. The price is subject to change if scope of work increases.

TERMS & CONDITIONS

We expect payments upon the completion of the job. There will be a 3% interest charge per month on late invoices.